

## CS Acrovyn® Models SMWS-20 and SMWS-20M

### Suggested Specifications | Section 10 26 00

#### Part 1 - General

##### 1.01 Summary

- A. This section includes the following types of wall protection systems:
  - 1. Corner Guards
- B. Related sections: The following sections contain requirements related to this section:
  - 1. Handrails, Bumper Guards, Crash Rails, Accent Rails, Wall Covering, Wall Panels, Door Protection; refer to section 10 26 00 “Wall and Door Protection”
  - 2. Blocking in walls for fasteners; refer to section 09 22 00 “Supports for Plaster and Gypsum Board”

##### 1.02 References

- A. National codes (IBC, UBC, SBCCI and BOCA)
- B. American Society for Testing and Materials (ASTM)
- C. California 01350 specification

##### 1.03 Submittals

- General: Submit the following in accordance with conditions of contract and Division 1 specification section 01 33 00 “Submittal Procedures”:
- A. Product data and detailed specifications for each system component and installation accessory required, including installation methods for each type of substrate.
  - B. Shop drawings showing locations, extent and installation details of corner guards. Show methods of attachment to adjoining construction.
  - C. Samples for verification purposes: Submit the following samples, as proposed for this work, for verification of color, finish and alignment:
    - 1. 6" (152.4mm) long sample of each model specified.
  - D. Maintenance data for wall protection system components for inclusion in the operating and maintenance manuals specified in Division 1.

##### 1.04 Quality Assurance

- A. Installer qualifications: Engage an installer who has no less than 3 years experience in installation of systems similar in complexity to those required for this project.
- B. Manufacturer’s qualifications: Not less than 5 years experience in the production of specified products and a record of successful in-service performance.
- C. Code compliance: Assemblies should conform to all applicable codes including IBC, UBC, SBCCI, BOCA and CA 01350.
- D. Single source responsibility: Provide all components of the wall protection system manufactured by the same company to ensure compatibility of color, texture and physical properties.

##### 1.05 Delivery, Storage and Handling

- A. Deliver materials to the project site in unopened original factory packaging clearly labeled to show manufacturer.
- B. Store materials in original, undamaged packaging in a cool, dry place out of direct sunlight and exposure to the elements. A minimum room temperature of 40°F (4°C) and a maximum of 100°F (38°C) should be maintained.
- C. Material must be stored flat.

##### 1.06 Project Conditions

- A. Materials must be acclimated in an environment of 65°-75°F (18°-24°C) for at least 24 hours prior to beginning the installation.
  - B. Installation areas must be enclosed and weatherproofed before installation commences.
- 1.07 Warranty**
- A. **Acrovyn 5-year Limited Warranty**
    - Applies to Interior Wall Protection orders that do not include recommended components or accessories
      - o Assemblies = Brackets, Hardware
      - o Accessories = Primer, Adhesive, Caulk, Trims & Moldings
  - B. **Limited Lifetime Systems Warranty**
    - Applies to CS Interior Wall Protection projects that include all recommended components and accessories related to CS Interior Wall Protection Products.
      - o Assemblies = Brackets, Hardware
      - o Accessories = Primer, Adhesive, Caulk, Trims & Moldings

## Part 2 - Products

### 2.01 Manufacturers

- A. Construction Specialties, 3 Werner Way, Lebanon, NJ 08833 USA 800-233-8493; email: [cet@csgroup.com](mailto:cet@csgroup.com)
- B. Drawings and specifications are based on manufacturer's literature from Construction Specialties, Inc. drawings and specifications unless otherwise indicated. Other manufacturers must be approved equal by Architect/Owner.

### 2.02 Materials

- A. Solid Wood Components: Shall be manufactured from plain sawn, FAS grade hardwood, kiln dried to a moisture content of 6% to 10%.
- A. Stainless steel components shall be fabricated from type 304 stainless steel with a #4 satin finish. Minimum strength and durability properties as specified in ASTM A276.
- B. Fasteners: All necessary fasteners to be supplied by the manufacturer.

### 2.03 Corner Guards

- A. Wood/Stainless Steel Corner Guards to be CS Acrovyn: Surface mounted assembly consisting of wood corner guard with stainless steel facing. All hardware shall be appropriate for wall construction.
  - 1. **Model SMWS-20 90° wood corner guard with 2 3/4" (69.9mm) legs and recessed stainless steel cover. Furnished cut-to-size only with standard stainless-steel end caps or optional wood end caps; both factory installed with Black horizontal reveals to allow for proper expansion and contraction of materials. Specify SMWS-20M for odd degree corners; stainless steel cap available for 135° corners only. Select from Renaissance™ wood species and finishes. FSC certified wood can be specified. Custom woods and finishes available. Optional powder coat finishes available for stainless steel components; select from standard powder coat finishes.**

### 2.04 Fabrication

- A. General: Fabricate wall protection systems to comply with requirements indicated for design, dimensions, detail, finish and member sizes. All based upon required field verified dimensions.
- B. Fabricate components with wood joints lightly chamfered.
- C. Provide surfaces free of chipping, dents and other imperfections.

### 2.05 Finishes

- A. All wood components shall be factory finished. Wood components to be final coated with water based, high solids, clear lacquer using a two coat process. Finish shall be in accordance with specified AWI finish system. Coverage shall be a minimum of 3-5 mils. Gloss shall be measured on 60° gloss meter as per ASTM D523.
- B. General: Comply with NAAMM "Metal Finishes Manual" for recommendations relative to applications and designations of finishes.

### Part 3 - Execution

#### 3.01 Examination

- A. Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
  - 1. Do not proceed until unsatisfactory conditions have been corrected.

#### 3.02 Preparation

- A. Surface preparation: Prior to installation, clean substrate to remove dirt, debris and loose particles. Perform additional preparation procedures as required by manufacturer's instructions.
- B. Protection: Take all necessary steps to prevent damage to material during installation as required in manufacturer's installation instructions.

#### 3.03 Installation

- A. Install the work of this section in strict accordance with the manufacturer's recommendations and the required field verified dimensions.
- B. Use only approved mounting hardware, and locating all components firmly into position, level and plumb.
- C. Temperature at the time of installation must be between 65°-75°F (18°-24°C) and be maintained for at least 48 hours after the installation.

#### 3.04 Cleaning

- A. General: Immediately upon completion of installation, clean rails and accessories in accordance with manufacturer's recommended cleaning method.
- B. Remove surplus materials, rubbish and debris resulting from installation as work progresses and upon completion of work.

#### 3.05 Protection

- A. Protect installed materials to prevent damage by other trades. Use materials that may be easily removed without leaving residue or permanent stains.