CS Acrovyn® Models LG-300, LG-250, LG-200, LG-150, LG-118, and LG-034

Suggested Specifications | Section 10 26 00

Part 1 - General

1.01 Summary

- A. This section includes the following types of wall protection systems:
 - 1. Corner Guards
- B. Related sections: The following sections contain requirements related to this section:
 - 1. Handrails, Bumper Guards, Crash Rails, Accent Rails, Wall Covering, Wall Panels, Door Protection; refer to section 10 26 00 "Wall and Door Protection"
 - 2. Blocking in walls for fasteners; refer to section 09 22 00 "Supports for Plaster and Gypsum Board"

1.02 References

- A. National codes (IBC, UBC, SBCCI, BOCA and Life Safety)
- **B.** American Society for Testing and Materials (ASTM)

1.03 Submittals

General: Submit the following in accordance with conditions of contract and Division 1 specification section 01 33 00 "Submittal Procedures":

- **A.** Product data and detailed specifications for each system component and installation accessory required, including installation methods for each type of substrate.
- **B.** Shop drawings showing locations, extent and installation details of corner guards. Show methods of attachment to adjoining construction.
- **C.** Samples for verification purposes: Submit the following samples, as proposed for this work, for verification of guard:
 - 6" (152.4mm) long sample of each model specified.
- **D.** Product test reports from a qualified independent testing laboratory showing compliance of each component with requirements indicated.
- E. Maintenance data for wall protection system components for inclusion in the operating and maintenance manuals specified in Division 1.

1.04 Quality Assurance

- **A.** Installer qualifications: Engage an installer who has no less than 3 years experience in installation of systems similar in complexity to those required for this project.
- **B.** Manufacturer's qualifications: Not less than 5 years experience in the production of specified products and a record of successful in-service performance.
- **C.** Code compliance: Assemblies should conform to all applicable codes including IBC, UBC, SBCCI, BOCA and Life Safety.
- **D.** Single source responsibility: Provide all components of the wall protection system manufactured by the same company to ensure compatibility of color, texture and physical properties.
- 1.05 Delivery, Storage and Handling

- **A.** Deliver materials to the project site in unopened original factory packaging clearly labeled to show manufacturer.
- **B.** Store materials in original, undamaged packaging in a cool, dry place out of direct sunlight and exposure to the elements. A minimum room temperature of 40°F (4°C) and a maximum of 100°F (38°C) should be maintained.
- C. Material must be stored flat.

1.06 Project Conditions

- **A.** Materials must be acclimated in an environment of 65°-75°F (18°-24°C) for at least 24 hours prior to beginning the installation.
- B. Installation areas must be enclosed and weatherproofed before installation commences.

1.07 Warranty

A. Acrovyn 5-year Limited Warranty

- Applies to Interior Wall Protection orders that <u>do not</u> include recommended components or accessories
 - o Assemblies = Brackets, Hardware
 - o Accessories = Primer, Adhesive, Caulk, Trims & Moldings

B. Limited Lifetime Systems Warranty

- Applies to CS Interior Wall Protection projects that include all recommended components and accessories related to CS Interior Wall Protection Products.
 - o Assemblies = Brackets, Hardware
 - o Accessories = Primer, Adhesive, Caulk, Trims & Moldings

Part 2 – Products

2.01 Manufacturer

- **A**. Construction Specialties, 3 Werner Way, Lebanon, NJ 08833 USA 800-233-8493; email: cet@c-sgroup.com
- **B.** Drawings and specifications are based on manufacturer's literature from Construction Specialties, Inc. unless otherwise indicated. Other manufacturers must be approved equal by Architect/Owner.

2.01 Materials

- A. Clear Polycarbonate: Corner guards shall be extruded from polycarbonate material with an impact resistance of 16 ft. lb./inch as tested per ASTM D-256, Notched Izod Test. Nominal thickness to be .050" (1.3mm) for 3/4" (19.1mm) legs; .075" (1.9mm) for 1-1/8" (28.6mm) and 1 1/2" (38.1mm) legs; and .10" (2.5mm) for 2" (50.8mm), 2 1/2" (63.5mm) and 3" (76.2mm) legs.
- **B.** Fasteners: All fasteners to be non-corrosive and compatible with polycarbonate. All necessary fasteners to be supplied by the manufacturer.

2.02 Corner Guards

A. Clear polycarbonate corner guards by CS Acrovyn: Surface mounted polycarbonate corner guards mounted with screws. Attachment hardware shall be appropriate for wall construction.

1. Model LG-300 90° surface mounted polycarbonate corner guard with 3" (76.2 mm) legs. Specify model LG-250 for 2 1/2" (63.5mm) legs, LG-200 for 2" (50.8mm) legs, LG-150 for 1 1/2" (38.1mm) legs, LG-118 for 1 1/8" (28.6mm) and LG-034 for 3/4" (19.1mm) legs. Odd angles available; specify LG-300M, LG-250M, LG-200M, LG-150M or LG-118M.

2.03 **Fabrication**

A. General: Fabricate wall protection systems to comply with requirements indicated for design, dimensions, detail, finish and member sizes.

Part 3 - Execution

3.01 Examination

- A. Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
- B. Do not proceed until unsatisfactory conditions have been corrected.

3.02 Preparation

- A. Surface preparation: Prior to installation, clean substrate to remove dirt, debris and loose particles. Perform additional preparation procedures as required by manufacturer's instructions.
- B. Protection: Take all necessary steps to prevent damage to material during installation as required in manufacturer's installation instructions.

3.03 Installation

- A. Install the work of this section in strict accordance with the manufacturer's recommendations, using only approved mounting hardware, and locating all components firmly into position, level and plumb.
- B. Temperature at the time of installation must be between 65°-75°F (18°-24°C) and be maintained for at least 48 hours after the installation.

3.04 Cleaning

- A. General: Immediately upon completion of installation, clean quards in accordance with manufacturer's recommended cleaning method.
- B. Remove surplus materials, rubbish and debris resulting from installation as work progresses and upon completion of work.

3.05 Protection

A. Protect installed materials to prevent damage by other trades. Use materials that may be easily removed without leaving residue or permanent stains.