| TOP RAIL WOOD FIN | ECIES: | | | | TOTAL L/F REQ'D | LEFT END CAPS | RIGHT END CAPS | O.S. REQ'D | |
|---|--|----------|----------------|-------------------------------------|--------------------|-----------------------------------|------------------------------|---------------|--|
| *BRACKETS:COLOR TO BE SELECTED FROM ONE OF C/S STANDARD COLORS. | | | | | | | | | |
| *BRACKETS ARE AVAILABLE WITH AN OPTIONAL POWDER COAT FINISH. PLEASE ADVISE POWDER COAT FINISH IF REQUIRED. | | | | | | | | | |
| WO | OOD HANDRAIL (24W240xxx) 3 3/8" [85.7mm] 4" [101.6mm] 0 0 0 0 0 0 0 0 0 | | 1 1/2" [38.1mr | | MIN STL (BY | OGGLE 812.8mm] O.0 ∄ | EEL APPING .AT HD BOLT | | |
| WALL CONDITION | SPECIFIED FASTENER | WALL | RETAINER | NUMBER | | | | | |
| STEEL STUD/GYPSUM WALL CONCRETE/CONCRETE BLOCK | 1/4-20 X 3" S/S FLAT HEAD BOLT WITH TOGGLE 1/4" X 1 3/4" S/S FLAT HEAD MASONRY ANCHOR | 3/4" | N/A N/A | 90H184002 90H390000 | | | | | |
| WOOD STUD/GYPSUM WALL | #14 X 3" S/S PHILLIPS FLAT HEAD WOOD SCREW | 7/32" | N/A | 90H538004 | | | | | |
| 20 GA. STEEL STUD/GYPSUM WALL (OSHPD) | 1/4 - 20 X 3" S/S FLAT HEAD BOLT 1/4" TOGGLER WING | 1/2" | N/A | 90H063002 90H062004 90M012000 | - | | | | |
| 16 GA. MIN STEEL STUD AND 16 GA. MIN STEEL STRAPPING / GYPSUM WALL CONSTRUCTION REQUIRED (TEK SCREWS) | 3M MOLDABLE FIRE PUTTY #14 X 3" PHILLIPS FLAT HEAD SELF DRILLING S/S TEK SCREW | N/A | N/A | 90M012000 90H230003 | | | | | |
| | | PROJECT: | | | | REVISI | REVISION: | | |
| Construction Specialties 6696 Route 405 Highway, Muncy PA 17756 (800) 233-8493 • Fax (570) 546-4692 • www.c-sgroup.com | | | JOB NO.: | | | | | | |
| | | | CUSTOMER: | | | | | | |
| | | | REP: | | | | DATE: | | |
| | | | DRAWN BY: | | | | SHEET NO: | | |

DOC#: TS-930-016 ISSUE DATE: 09/12/03 REV DATE: 02/14/2023