

**| Suggested Specifications | Section 10 26 00
CS Acrovyn® Model FRWS-2**

Part 1 - General

1.01 Summary

- A.** This section includes the following types of wall protection systems:
 - 1.** Accent Rails
- B.** Related sections: The following sections contain requirements related to this section:
 - 1.** Handrails, Corner Guards, Bumper Guards, Crash Rails, Wall Covering, Wall Panels, Door Protection; refer to section 10 26 00 "Wall and Door Protection"
 - 2.** Blocking in walls for fasteners; refer to section 09 22 00 "Supports for Plaster and Gypsum Board"

1.02 References

- A.** National codes (IBC, UBC, SBCCI, BOCA and Life Safety)
- B.** American Society for Testing and Materials (ASTM)
- C.** California 01350 specification

1.03 Submittals

General: Submit the following in accordance with conditions of contract and Division 1 specification section 01 33 00 "Submittal Procedures":

- A.** Product data and detailed specifications for each system component and installation accessory required, including installation methods for each type of substrate.
- B.** Shop drawings showing locations, extent, and installation details of accent rails. Show methods of attachment to adjoining construction.
- C.** Samples for verification purposes: Submit the following samples, as proposed for this work, for verification of color, finish and end cap attachment and alignment:
 - 1.** 12" (304.8mm) long sample of each model specified including end cap.
- D.** Maintenance data for wall protection system components for inclusion in the operating and maintenance manuals specified in Division 1.

1.04 Quality Assurance

- A.** Installer qualifications: Engage an installer who has no less than 3 years' experience in installation of systems similar in complexity to those required for this project.
- B.** Manufacturer's qualifications: Not less than 5 years' experience in the production of specified products and a record of successful in-service performance.
- C.** Code compliance: Assemblies should conform to all applicable codes including IBC, UBC, SBCCI, BOCA, Life Safety and CA 01350.
- D.** Fire performance characteristics: Provide wood and metal components tested in accordance with ASTM E84 for Class A/1 fire characteristics.
- E.** Single source responsibility: Provide all components of the wall protection system manufactured by the same company to ensure compatibility of color, texture, and physical properties.

1.05 Delivery, Storage and Handling

- A.** Deliver materials to the project site in unopened original factory packaging clearly labeled to show manufacturer.
- B.** Store materials in original, undamaged packaging in a cool, dry place out of direct

sunlight and exposure to the elements. A minimum room temperature of 40°F (4°C) and a maximum of 100°F (38°C) should be maintained.

C. Material must be stored flat.

1.06 Project Conditions

A. Materials must be acclimated in an environment of 65°-75°F (18°-24°C) for at least 24 hours prior to beginning the installation.

B. Installation areas must be enclosed and weatherproofed before installation commences.

1.07 Warranty

A. Acrovyn 5-year Limited Warranty

- Applies to Interior Wall Protection orders that do not include recommended components or accessories
 - Assemblies = Brackets, Hardware
 - Accessories = Primer, Adhesive, Caulk, Trims & Moldings

B. Limited Lifetime Systems Warranty

- Applies to CS Interior Wall Protection projects that include all recommended components and accessories related to CS Interior Wall Protection Products.
 - Assemblies = Brackets, Hardware
 - Accessories = Primer, Adhesive, Caulk, Trims & Moldings

Part 2 - Products

2.01 Manufacturers

A. Interior surface protection products specified herein and included on the submittal drawings shall be manufactured by Construction Specialties, Inc., 3 Werner Way, Lebanon, NJ 08833 USA 800-233-8493; email: cet@c-sgroup.com

B. Drawings and specifications are based on manufacturer's literature from Construction Specialties, Inc. drawings and specifications unless otherwise indicated. Other manufacturers must be approved equal by Architect/Owner.

2.02 Materials

A. Solid Wood Components: Shall be manufactured from plain sawn, FAS grade hardwood, kiln dried to a moisture content of 6% to 10%.

B. Stainless steel components shall be fabricated from type 304 stainless steel with a #4 satin finish; minimum strength and durability properties as specified in ASTM A240.

2.03 Accent Rails

A. Wood/Stainless Steel Accent Rails to be CS Acrovyn: Surface mounted assembly consisting of wood rail furnished with stainless steel trim and end caps. Attachment hardware shall be appropriate for wall construction.

- 1. Model FRWS-2 2" (50.8mm) high solid wood accent rail assembly with (2) rows of 1/8" (3.2mm) wide stainless-steel inserts. Furnished cut-to-size only with standard stainless steel end caps or optional wood end caps; both factory installed with Black vertical reveals to allow for proper expansion and contraction of materials. Select from one of Renaissance™ Wood species and finishes. Custom woods and finishes available.**

2.04 Finishes

- A.** All wood components shall be factory finished. Wood components to be final coated with water based, high solids, clear lacquer using a two-coat process. Finish shall be in accordance with specified AWI finish system. Coverage shall be a minimum of 3-5 mils. Gloss shall be measured on 60° gloss meter as per ASTM D523.
- B.** General: Comply with NAAMM “Metal Finishes Manual” for recommendations relative to applications and designations of finishes.

2.05 Fabrication

- A.** General: Fabricate wall protection systems to comply with requirements indicated for design, dimensions, detail, finish, and member sizes. All based upon required field verified dimensions.
- B.** Preassemble components in shop as much as possible to minimize field assembly.
- C.** Fabricate components with wood joints lightly chamfered. Provide surfaces free of chipping, dents, and other imperfections.

Part 3 - Execution

3.01 Examination

- A.** Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
 - 1.** Do not proceed until unsatisfactory conditions have been corrected.

3.02 Preparation

- A.** Surface preparation: Prior to installation, clean substrate to remove dirt, debris, and loose particles. Perform additional preparation procedures as required by manufacturer's instructions.
- B.** Protection: Take all necessary steps to prevent damage to material during installation as required in manufacturer's installation instructions.

3.03 Installation

- A.** Install the work of this section in strict accordance with the manufacturer's recommendations and the required field verified dimensions.
- B.** Use only approved mounting hardware, and locating all components firmly into position, level and plumb.
- C.** Temperature at the time of installation must be between 65°-75°F (18°-24°C) and be maintained for at least 48 hours after the installation.

3.04 Cleaning

- A.** General: Immediately upon completion of installation, clean rails, and accessories in accordance with manufacturer's recommended cleaning method.
- B.** Remove surplus materials, rubbish and debris resulting from installation as work progresses and upon completion of work.

3.05 Protection

- A.** Protect installed materials to prevent damage by other trades. Use materials that may be easily removed without leaving residue or permanent stains.