# CS Acrovyn<sup>®</sup> 4000 Models FS-20N and FS-20RN

Suggested Specifications | Section 10 26 00

## Part 1 - General

### 1.01 Summary

- A. This section includes the following types of wall protection systems:
  1. Corner Guards
- **B.** Related sections: The following sections contain requirements related to this section:
  - 1. Handrails, Bumper Guards, Crash Rails, Accent Rails, Wall Covering, Wall Panels, Door Protection; refer to section 10 26 00 "Wall and Door Protection"
  - **2.** Blocking in walls for fasteners; refer to section 09 22 00 "Supports for Plaster and Gypsum Board"

### 1.02 References

- A. National codes (IBC, UBC, SBCCI, BOCA and Life Safety)
- B. American Society for Testing and Materials (ASTM)
- C. Underwriters Laboratories (UL)
- D. California 01350 specification

### 1.03 Submittals

General: Submit the following in accordance with conditions of contract and Division 1 specification section 01 33 00 "Submittal Procedures":

- **A.** Product data and detailed specifications for each system component and installation accessory required, including installation methods for each type of substrate.
- **B.** Shop drawings showing locations, extent and installation details of corner guards. Show methods of attachment to adjoining construction.
- **C.** Samples for verification purposes: Submit the following samples, as proposed for this work, for verification of color, texture and pattern:
  - 1. 10" (254mm) long sample of each model specified.
- **D.** Product test reports from a qualified independent testing laboratory showing compliance of each component with requirements indicated.
- **E.** Maintenance data for wall protection system components for inclusion in the operating and maintenance manuals specified in Division 1.

## 1.04 Quality Assurance

- **A.** Installer qualifications: Engage an installer who has no less than 3 years' experience in installation of systems similar in complexity to those required for this project.
- **B.** Manufacturer's qualifications: Not less than 5 years' experience in the production of specified products and a record of successful in-service performance.
- **C.** Code compliance: Assemblies should conform to all applicable codes including IBC, UBC, SBCCI, BOCA, Life Safety and CA 01350 (exception: fire barrier).
- **D.** Fire performance characteristics: Provide engineered PVC FREE wall protection system components with UL label indicating that they are identical to those tested in accordance with ASTM E84 for Class A/1 characteristics listed below:
  - 1. Flame spread: 25 or less
  - 2. Smoke developed: 450 or less
- E. Fire performance characteristics: Provide engineered PVC FREE wall protection units with fire barrier that are identical to those tested in accordance with UL-263 (E-119) for one hour or two hour rated installation.

- **F.** Chemical and stain resistance: Provide wall protection system components with chemical and stain resistance in accordance with ASTM D543.
- **G.** Impact strength: Provide wall protection components that have been tested for impact using a ram-type impact test in accordance with the applicable provisions of ASTM F476 -84 .
- **H.** Color match: Provide wall protection components that are color matched in accordance with the following:
  - 1. Delta Ecmc of no greater than 1.0 using CIELab color space. (Specifier note: Construction Specialties' colors are matched under cool white fluorescent lighting and computer controlled within manufacturing tolerances. Color may vary if alternate lighting sources are present.)
- I. Single source responsibility: Provide all components of the wall protection system manufactured by the same company to ensure compatibility of color, texture and physical properties.

## 1.05 Delivery, Storage and Handling

- **A.** Deliver materials to the project site in unopened original factory packaging clearly labeled to show manufacturer.
- B. Store materials in original, undamaged packaging in a cool, dry place out of direct sunlight and exposure to the elements. A minimum room temperature of 40°F (4°C) and a maximum of 100°F (38°C) should be maintained.
- C. Material must be stored flat.

# 1.06 Project Conditions

- **A.** Materials must be acclimated in an environment of 65°-75°F (18°-24°C) for at least 24 hours prior to beginning the installation.
- **B.** Installation areas must be enclosed and weatherproofed before installation commences.

# 1.07 Warranty

# A. Acrovyn 5-year Limited Warranty

- □ Applies to Interior Wall Protection orders that <u>do not</u> include recommended components or accessories
  - Assemblies = Brackets, Hardware
  - Accessories = Primer, Adhesive, Caulk, Trims & Moldings

# B. Limited Lifetime Systems Warranty

- □ Applies to CS Interior Wall Protection projects that include all recommended components and accessories related to CS Interior Wall Protection Products.
  - Assemblies = Brackets, Hardware
  - Accessories = Primer, Adhesive, Caulk, Trims & Moldings

# Part 2 – Products

# 2.01 Manufacturer

- A. Construction Specialties, 3 Werner Way, Lebanon, NJ 08833 USA 800-233-8493; email: cet@c-sgroup.com
  - **B.** Drawings and specifications are based on manufacturer's literature from

Construction Specialties, Inc. unless otherwise indicated. Other manufacturers must be

## approved equal by Architect/Owner.

## 2.02 Materials

**A.** Engineered PVC FREE: Extruded material should be high-impact Acrovyn 4000 with Shadowgrain texture, nominal .078" (1.98mm) thickness. Chemical and stain resistance



should be per ASTM D543 standards as established by the manufacturer. Colors to be indicated in the finish schedule from one of manufacturer's available colors and patterns.

- **A.** Aluminum: Extruded aluminum retainers should be 6063-T6 alloy, nominal .070" (1.78mm) thickness. Minimum strength and durability properties as specified in ASTM B221.
- **B.** Fasteners: All fasteners to be non-corrosive and compatible with aluminum retainers. All necessary fasteners to be supplied by the manufacturer.

### 2.03 Corner Guards

- **A.** Engineered PVC FREE Corner Guards to be CS Acrovyn: Flush mounted, tamper resistant, guards consisting of continuous aluminum retainer with snap-on Acrovyn 4000 cover. Retainer to be taped and spackled into adjacent drywall. Extruded aluminum base and closure gasket where indicated. Attachment hardware shall be appropriate for wall construction.
  - Model FS-20N 90° flush mounted, tamper resistant, corner guard with 3" (76.6mm) legs and 1/4" (6.4 mm) radiused cover. For optional integral fire barrier, specify FS-20RN 1HR for one hour fire rated installation or FS-20RN 2HR for two hour fire rated installation. Select from one of Acrovyn™ solid colors, Acrovyn™ Woodgrains or Acrovyn™ Brushed Metals simulated patterns. [Specifier note: refer to the Acrovyn Cradle to Cradle Product Summary at www.acrovyn.com/c2c to determine which model variations, colors and patterns are Cradle to Cradle Certified™ Gold or Silver (exception: fire barrier). Cradle to Cradle Certified™ is a certification mark licensed by the Cradle to Cradle Products Innovation Institute.]

#### 2.04 Fabrication

**A.** General: Fabricate wall protection systems to comply with requirements indicated for design, dimensions, detail, finish and member sizes.

#### Part 3 - Execution

#### 3.01 Examination

- **A.** Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
  - 1. Do not proceed until unsatisfactory conditions have been corrected.

## 3.02 Preparation

- **A.** Surface preparation: Prior to installation, clean substrate to remove dirt, debris and loose particles. Perform additional preparation procedures as required by manufacturer's instructions.
- **B.** Protection: Take all necessary steps to prevent damage to material during installation as required in manufacturer's installation instructions.

## 3.03 Installation

- **A.** Install the work of this section in strict accordance with the manufacturer's recommendations, using only approved mounting hardware, and locating all components firmly into position, level and plumb.
- **B.** Temperature at the time of installation must be between 65°-75°F (18°-24°C) and be maintained for at least 48 hours after the installation.

## 3.04 Cleaning

- **A.** General: Immediately upon completion of installation, clean guards, and accessories in accordance with manufacturer's recommended cleaning method.
- **B.** Remove surplus materials, rubbish and debris resulting from installation as work progresses and upon completion of work.

#### 3.05 Protection

**A.** Protect installed materials to prevent damage by other trades. Use materials that may be easily removed without leaving residue or permanent stains.





c-sgroup.com 800.233.849