

CS Acrovyn® Models FR-252N

Suggested Specifications | Section 09 72 00
Canadian Specifications

Part 1 - General

1.01 Summary

- A. This section includes the following types of wall protection systems:
 - 1. Accent Rails
- B. Related sections: The following sections contain requirements related to this section:
 - 1. Handrails, Bumper Guards, Crash Rails, Corner Guards, Wall Coverings, Wall Panels, Door Protection; refer to section 10 26 00 "Wall and Door Protection"
 - 2. Blocking in walls for fasteners; refer to section 09 22 00 "Supports for Plaster and Gypsum Board"

1.02 References

- A. National Building Code of Canada (NBC 2010)
- B. National codes (IBC, UBC, SBCCI, BOCA and Life Safety)
- C. American Society for Testing and Materials (ASTM)
- D. Underwriters Laboratories (UL)
- E. California 01350 specification

1.03 Submittals

- A. General: Submit the following in accordance with conditions of contract and Division 1 specification section 01 33 00 "Submittal Procedures".
- B. Product data and detailed specifications for each system component and installation accessory required, including installation methods for each type of substrate.
- C. Shop drawings showing locations, extent and installation details of accent rails. Show methods of attachment to adjoining construction.
- D. Samples for verification purposes: Submit the following samples, as proposed for this work, for verification of color, texture, pattern and end cap alignment.
 - 1. 6" (152.4mm) sample of each model specified including end cap and mounting hardware. Sample color is White Papyrus.
- E. Product test reports from a qualified independent testing laboratory showing compliance of each component with requirements indicated.
- F. Maintenance data for wall protection system components for inclusion in the operating and maintenance manuals specified in Division 1.

1.04 Quality Assurance

- A. Installer qualifications: Engage an installer who has no less than 3 years experience in installation of systems similar in complexity to those required for this project.
- B. Manufacturer's qualifications: Not less than 5 years experience in the production of specified products and a record of successful in-service performance.
- C. Code compliance: Assemblies should conform to all applicable codes including NBC 2010, IBC, UBC, SBCCI, BOCA, Life Safety and CA 01350.
- D. Fire performance characteristics: Provide engineered PVC-Free wall protection system components tested to Canadian Required CAN/ULC S102.2, "Test for Surface Burning Characteristics of Flooring, Floor Coverings, and Miscellaneous Materials and Assemblies" with results listed below:
 - 1. Flame spread: 150 or less

- 2. Smoke developed: 300 or less
 - E. Impact Strength: Provide assembled wall protection units that have been tested in accordance with the applicable provisions of ASTM F476.
 - F. Chemical and stain resistance: Provide wall protection system components with chemical and stain resistance in accordance with ASTM D543.
 - G. Color match: Provide wall protection components that are color matched in accordance with the following:
 - 1. Delta Ecmc of no greater than 1.0 using CIELab color space. (Specifier note: Construction Specialties' colors are matched under cool white fluorescent lighting and computer controlled within manufacturing tolerances. Color may vary if alternate lighting sources are present.)
 - H. Single source responsibility: Provide all components of the wall protection system manufactured by the same company to ensure compatibility of color, texture and physical properties.
- 1.05 Delivery, Storage and Handling**
- A. Deliver materials to the project site in unopened original factory packaging clearly labeled to show manufacturer.
 - B. Store materials in original, undamaged packaging in a clean, dry place out of direct sunlight and exposure to the elements. A minimum room temperature of 40°F (4°C) and a maximum of 100°F (38°C) should be maintained.
 - C. Materials must be stored flat.
- 1.06 Project Conditions**
- A. Materials must be acclimated in an environment of 65-75°F (18-24°C) for at least 24 hours prior to beginning the installation.
 - B. Installation areas must be enclosed and weatherproofed before installation commences.
- 1.07 Warranty**
- A. **Acrovyn 5-year Limited Warranty**
 - 1. Applies to Interior Wall Protection orders that do not include recommended components accessories
 - a) Assemblies = Brackets, Hardware
 - b) Accessories = Primer, Adhesive, Caulk, Trims & Moldings
 - B. **Limited Lifetimes System Warranty**
 - 1. Applies to CS Interior Wall Protection projects that include all recommended components and accessories related to CS Interior Wall Protection Products.
 - a) Assemblies = Brackets, Hardware
 - b) Accessories = Primer, Adhesive, Caulk, Trims & Moldings

Part 2 - Products

2.01 Manufacturers

- A. Interior surface protection products specified herein and included on the submittal drawings shall be manufactured by Construction Specialties, Inc., 3 Werner Way, Lebanon, NJ 08833 USA 800-233-8493; email: cet@c-sgroup.com
- B. Drawings and specifications are based on manufacturer's literature from Construction Specialties, Inc. drawings and specifications unless otherwise indicated. Other manufacturers must be approved equal by Architect/Owner.

2.02 Materials

- A. Accent Rails to be Acrovyn 4000 by Construction Specialties: Surface mounted assembly consisting of .040" (1.02mm) thick engineered PVC-Free Acrovyn 4000 sheet with suede texture to be factory bonded to the face side and edges of a 3/4"

(19.05mm) medium density fiber board core with no added urea formaldehyde. Chemical and stain resistance should be per ASTM D543 standards as established by the manufacturer. Colors to be indicated in the finish schedule from one of manufacturer's standard color range.

1. Model FR-252N 2-1/2" (63.5 mm) engineered PVC-Free colonial style accent rail. Select from one of Acrovyn solid colors, Acrovyn Woodgrains or Acrovyn Brushed Metals simulated patterns.

2.03 Fabrication

- A. General: Fabricate wall protection systems to comply with requirements indicated for design, dimensions, detail, finish and sizes.

Part 3 - Execution

3.01 Examination

- A. Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
 1. Do not proceed until unsatisfactory conditions have been corrected.

3.02 Preparation

- A. Surface preparation: Prior to installation, clean substrate to remove dirt, debris and loose particles. Perform additional preparation procedures as required by manufacturer's instructions.
- B. Protection: Take all necessary steps to prevent damage to material during installation as required in manufacturer's installation instructions.

3.03 Installation

- A. Install the work of this section in strict accordance with the manufacturer's recommendations, using only approved mounting hardware, and locating all components firmly into position, level and plumb.
- B. Temperature at the time of installation must be between 65-75°F (18-24°C) and be maintained for at least 48 hours after the installation.

3.04 Cleaning

- A. General: Immediately upon completion of installation, clean rails and accessories in accordance with manufacturer's recommended cleaning method.
- B. Remove surplus materials, rubbish and debris resulting from installation as work progresses and upon completion of work.

3.05 Protection

- A. Protect installed materials to prevent damage by other trades. Use materials that may be easily removed without leaving residue or permanent stains.